

15-145-01103-0000

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 5 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Co., Inc.

Complete Address: 410 4th Nat'l Bank Bldg., Wichita, Kansas

Lease Name L. J. Schartz Well No. 1

Location SW SW NE SWSWNE Sec. 8 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4350

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 11A Day 3 Month 6 Year 1969

The Above well was plugged as follows:

Total depth 4350' 8 5/8 csg set at 214' cwc 175 sk.

5 1/2 csg set at 4349' cw 175 sk cmt.

5 1/2 csg top perf. 4205

Filled 5 1/2 csg W/sd (4190-4350) Dumped 5 sk cmt W/dump bailer. (4150-4190)

Cutoff and recovered 3200' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/5/69  
INV. NO. 9892-4

Signed: Red J. Mason  
Well Plugging Supervisor