

15-145-00832-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name A. L. Abercrombie, Incorporated,

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Clark Well No. 3

Location NW-NW-NW Sec. 8 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4310'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Halliburton Oil Well Cementing,

Address Great Bend, Kansas. License No. _____

Operation Completed: Hour 2:00 PM Day 21 Month 6 Year 1969

The above well was plugged as follows:

232'--8 5/8" Surface casing, cement circulated with 200 Sx.
4308'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to
4270'. Top perforations from 4230' to 4240'.

Sanded well back to 4200' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well with 5 sacks hulls, then 20 sacks gel and followed with 130 Sx.
cement. Maximum pump-in pressure--100#. Final shut-in pressure--25#. (recovered
3274' 5 1/2" casing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 7-1-69

INV. NO. 8-W