

15-145-01183-0600

Form CP-3
Rev. 6-26-62

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply
Complete Address: Box 562 Great Bend, Kansas
Lease Name Showalter Well No. 1
Location SE SE SE Sec. 6 Twp. 23 Rge. (E) (W) 17
County Pawnee Total Depth 4320
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Ace Pipe Pulling Co
Address: Great Bend, Kans License No. 2
Operation Completed: Hour 10AM Day 9 Month 7 Year 64

The Above well was plugged as follows:

8 5/8" 232' circulated with cement - 5 1/2" 4319' with 100 sax cement - PB
4200' - perforated 4183'

Filled with sand to 4170', set 4 sax cement with dump bailer - pulled
3570' 5 1/2" - pumped hole full heavy mud (40 sax Gel) pumped wiper plug
followed by 100 sax cement - cement went down 25' - filled with 7 sax cement
by hand to bottom cellar.

Mudding and cementing by Ace Company pump truck.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edon Pilly*
Well Plugging Supervisor

INVOICED

DATE 7/16/64
INV. NO. 9486-W