

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-145-01100-00-01

Rec'd 3115'

RECEIVED
STATE CORPORATION COMMISSION
AUG 14 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bovaird Supply Company

Complete Address Box 48 Great Bend, Kansas 67530

Lease Name Godfrey (SWD) Well No. 3

Location NE SE NW Sec. 7 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4311'

Abandoned Oil Well Gas Well Input Well SWD Well XX D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 12 N Day 11 Month 8 Year 1972

The above well was plugged as follows:

Total depth 4311' 8 5/8 csg set at 220' cwc 200 sk.

5 1/2 csg set at 4309' cw 150 sk cmt.

5 1/2 csg perf. (4222-4230)

Filled 5 1/2 csg W/sd (4200-4311) dumped 5 sk cmt W/dump bailer. (4165-4200)

Cutoff and recovered 3115' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/500 lbs hulls, released 8 5/8 plug
and pumped 100 sk comm cmt W/2% CC.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Muesel
Well Plugging Supervisor

INVOICED

DATE 8-15-72

INV. NO. 6162-W