

15-145-01101-00-01

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name National Cooperative Refinery Association

Complete Address Box 6 Great Bend, Kansas 67530

Lease Name Godfrey Well No. 2

Location NE NE SW Sec. 7 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4345

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas 67530 License No. 49

Operation Completed: Hour 12:30P Day 18 Month 12 Year 1969

The above well was plugged as follows:

Total Depth 4345' 8 5/8 csg set at 714' cwc. 400 sk.

5 1/2 csg set at 4314' cw 100 sk cmt.

5 1/2 csg PBD 4295' with top perf. (4240)

Filled 5 1/2 csg W/sd (4200-4295) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recovered 2396' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/500 lbs hulls, plug and 100 sk

comm. Cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED RECEIVED
STATE CORPORATION COMMISSION
DATE 12/19/69 DEC 19 1969
INV. NO. 1086-W CONSERVATION DIVISION
Wichita, Kansas

Signed: Bio T. Massing
Well Plugging Supervisor