

15-145-00830-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Kewanee Oil Company

Complete Address Box 360 Hosington, Kansas 67544

Lease Name Schartz "B" Well No. 6

Location SE NW NE Sec. 7 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4360'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 1:15 P Day 16 Month 11 Year 1971

The above well was plugged as follows:

Total Depth 4360' 8 5/8 csg set at 205' cwc 175 sk.

5 1/2 csg set at 4359' cw 175 sk cmt.

5 1/2 csg PBTD 4329 1/2 with top perf. (4227-4239)

Filled 5 1/2 csg W/sd (4200-4329 1/2) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recovered 2830' of 5 1/2 csg.

Pumped down 8 5/8 csg with 10 sk gel & water W/300 lbs hulls, released plug and

pumped 100 sk comm cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. E. Messer
Well Plugging Supervisor

DATE 11-29-71

INV. NO. 4689-W