

State of Kansas



FORM CP-2

15.159.21027.00.00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water

WICHITA, KANSAS 67202

November 6, 1980

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Bennie Lucero of Salazar Bros. Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Buckeye Energy, Inc.

Complete Address: 226 Western United Life Bldg, Midland, Texas

Lease Name: Marion Well No. 22-1

Location: SE SW SE Sec. 22 Twp. 19 Rge. 10 (E) (W)

County: Rice Total Depth: 3302'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Lucero was instructed to plug the well as follows:

8 5/8" - 260' - 75 sacks. Fill hole with mud. Pump 50 sacks cement through drill pipe at 450'. Pump 30 sacks cement through drill pipe at 240'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent

RECEIVED
NOV 17 1980
CONSERVATION DIVISION
WICHITA, KANSAS