

State of Kansas



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1968
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

April 11, 1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casng Pulling Co., Inchas this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: R. G. Smith

Complete Address: 602 Rule Bldg., Wichita, Kansas 67202

Lease Name: Schmit Well No. 1

Location: SW NE SE Sec. 10 Twp. 19 Rge. 10 (E)(W) X

County: Rice Total Depth 2950' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:
Fill hole with sand to 2900' and cement with 4 sacks. Pull 4 1/2" casing
to 600'. Pump 5 sacks gel mud through casing at 600'. Pump 25 sacks
cement through casing at 500'. Pump 5 sacks gel mud through casing at
300'. Pump 25 sacks cement through casing at 200'. Fill hole with mud
to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks
cement.

Very truly yours,

[Signature]
Conservation Division Agent