

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg.
 WICHITA, KANSAS 67202

RECEIVED
 DEC 30 1968
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

December 22, 1968

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Clarence Michaels of Sage Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Michaels guarantees payment of the plugging fee.

Operator's full Name: Keener Oil Company

Complete Address: 406 N. B. T. Bldg., Tulsa, Oklahoma

Lease Name: Clary Well No. 1

Location: SW NE SW Sec. 36 Twp. 19 Rge. 9 (E)(W) X

County: Rice Total Depth 3400' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Michaels was instructed to plug the well as follows:

Fill hole with mud to 235'. Push plug and 1/4 sack hulls to 235' and
cement hole with 25 sacks cement through drill pipe. Fill hole with mud
to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

William J. Loman
 Conservation Division Agent