

State of Kansas



FORM CP-2

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

July 15, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Duane Popp of Future Drilling, Inc. has this
date requested permission to plug the following described well:

Operator's Full Name: Pioneer Operations Company, Inc.

Complete Address: Box 272, Russell, Kansas 67665

Lease Name: Hall Well No. 2

Location: C W/2 SW SE Sec. 31 Twp. 19 Rge. 9 (EX) (W)

County: Rice Total Depth: 3243'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereafter indicated:

Mr. Popp was instructed to plug the well as follows:

8-5/8"-217'-180 sacks Circulate and fill hole with mud. Pump 50 sacks
cement through drill pipe at 450'. Pump 40 sacks cement through drill
pipe at 240'. Push plug and 1/2 sack hulls to 40' and cap hole with 10
sacks cement. Cement rathole with 10 sacks cement.

Orders by Duane Rankin

Very truly yours,

Albert J. Leonard
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

7-17-81 JUN 17 1981

CONSERVATION DIVISION
Wichita, Kansas