


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Rice County. Sec. 3 Twp. 19 Rge. 10 (E) W (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NE NW  
Lease Owner Lebsack Oil Co.  
Lease Name Schmidt Well No. 3  
Office Address Box 479, Hays, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced September 7 \_\_\_\_\_ 1961  
Plugging completed September 9 \_\_\_\_\_ 1961  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Jones  
Producing formation Arb. Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3296 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE  | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 174'   | none       |
|           |         |      |    | 5 1/2 | 3278   | 2346       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bridge plug at 3025'  
Filled hole with sand to 3000'  
Dumped 5 sacks cement  
Shot pipe @2328'  
Pumped 5 sacks cement and 20 sacks of mud  
Pumped 5 sacks cement and 8 sacks of mud

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 10 1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pipe Pullers Inc.  
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Pipe Pullers, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Keller

(Address)

SUBSCRIBED AND SWORN TO before me this 5 day of October, 1961

My commission expires December 18, 1962

Juanita R. Myers

Notary Public.



WELL LOG

CARL LEBSACK ET AL, OWNERS - W. C. Schmidt #3  
 SW 1/4 NE 1/4 NW 1/4 Section 3, Township 19, Range 10W,  
 Rice County, Kansas

Elevation: 1732 DF (Est)

Figures indicate bottom of formation  
 0 to 25 sand

Pipe Record:

8 5/8" set at 114'  
 5 1/2" set at 3280'

Tops: RBM

Heebner 2792 (-1058)  
 Brown Lime 2915 (-1181)  
 Lansing 2934 (-1200)  
 Conglomerate 3251 (-1517)  
 Arbuckle 3274 (-1540)

75 clay and shale  
 330 shale and shells  
 434 red bed  
 462 anhydrite  
 920 shale and shells  
 1180 salt  
 1528 shale and shells  
 1550 sand and shale  
 1575 shale and shells  
 1605 sand and lime  
 2025 lime and shale  
 2525 shale and shells  
 2760 lime and shale  
 2792 lime  
 2796 Heebner  
 3251 lime  
 3274 conglomerate  
 3280 arbuckle  
 3280 Total Rotary Depth

Rotary Commenced 3-7-52  
 Completed 3-16-52

STATE OF KANSAS )  
 ) ss  
 COUNTY OF BARTON )

I, M. M. Shropshire, Drilling Superintendent of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

M. M. Shropshire

Subscribed and Sworn to before me this 14th day of May, 1952.

George A. Meyer  
 Notary Public

My commission expires Feb. 10, 1955.

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 11 1961  
 CONSERVATION DIVISION  
 Wichita, Kansas

WELL LOG

CARL LEBSACK ET AL, OWNERS - W. C. Schmidt #3  
SW 1/4 NE 1/4 NW 1/4 Section 3, Township 19, Range 10W,  
Rice County, Kansas

|                           |   |   |                         |
|---------------------------|---|---|-------------------------|
| Elevation: 1732 DF (Est)  | 0 | Figures indicate bottom of formation to | 25 sand                 |
|                           |   |   | 75 clay and shale       |
| Pipe Record:              |   |   | 330 shale and shells    |
|                           |   |   | 434 red bed             |
| 8 5/8" set at 144'        |   |   | 462 anhydrite           |
| 5 1/2" set at 3280'       |   |   | 920 shale and shells    |
|                           |   |   | 1180 salt               |
| Tops: RBM                 |   |   | 1528 shale and shells   |
|                           |   |   | 1550 sand and shale     |
| Heebner 2792 (-1058)      |   |   | 1575 shale and shells   |
| Brown Lime 2915 (-1181)   |   |   | 1605 sand and lime      |
| Lansing 2934 (-1200)      |   |   | 2025 lime and shale     |
| Conglomerate 3251 (-1517) |   |   | 2525 shale and shells   |
| Arbuckle 3274 (-1540)     |   |   | 2760 lime and shale     |
|                           |   |   | 2792 lime               |
|                           |   |   | 2796 Heebner            |
| Rotary Commenced 3-7-52   |   |   | 3251 lime               |
| Completed 3-16-52         |   |   | 3274 conglomerate       |
|                           |   |   | 3280 arbuckle           |
|                           |   |   | 3280 Total Rotary Depth |

STATE OF KANSAS )  
                          ) ss  
COUNTY OF BARTON )

I, M. M. Shropshire, Drilling Superintendent of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

M. M. Shropshire

Subscribed and Sworn to before me this 14th day of May, 1952.

George A. Meyer  
Notary Public

My commission expires Feb. 10, 1955.

**RECEIVED**  
STATE CORPORATION COMMISSION

OCT 10 1961  
CONSERVATION DIVISION  
Wichita, Kansas