


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rice County. Sec. 36 Twp. 19 Rge. (E) 9 (W)
Location as "NE/CNW/SW" or footage from lines SW NW NW
Lease Owner J. C. Dozier
Lease Name Markle Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 7/28 19 52
Application for plugging filed 8/1 19 52
Application for plugging approved 8/1 19 52
Plugging commenced 9-6-52 19
Plugging completed 9-9-52 19
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruell Durkee
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5-1/2"	3379	2480'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole from 2990' to 2955' and ran 6 sacks of cement. Bailed hole to 155', set 10' rock bridge at 155' and ran 15 sacks of cement. Mudded hole to 30', set 10' rock bridge and ran 5 sacks of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
J. C. Dozier (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
1307 Union National Bank Bldg.
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September, 1952.
Verdina B. Rutledge
Notary Public.

My commission expires March 15, 1956.

PLUGGING
FILE SEC. 36 T. 19 R. 12
BOOK PAGE 34 LINE 20

RECEIVED
STATE CORPORATION COMMISSION
SEP 25 1952
CONSERVATION DIVISION

CONTRACTOR'S WELL LOG

OPERATOR Dozier Oil Co FARM NAME Markle #1 WELL NO. 1
 LOCATION SW/4 NW/4 NW/4 36-19-9W COUNTY Rice STATE Kansas
 COMMENCEMENT DATE July 17, 1952 COMPLETION DATE 7/27/52

LOG OF WELL

* All measurements from top of rotary bushing

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	161	Surface Soil		
161	295	Red Bed		
295	310	Sand		
310	850	Shale-Shells	0° - 500'	
850	1100	Salt	1/4° - 1005'	
1100	1380	Lime & Shale		
1380	1480	Sandy lime		
1480	1980	Lime shale		
1980	2440	Shale Shells	1/2° - 2000'	
2440	2470	Lime shale		
2470	2730	Lime	3/4° - 2570'	
2730	2735	Shale		
2735	2895	Lime shale		
2895	3205	Lime		
3205	3315	Shale Sandy lime		
3315	3387	Sand		
3387	3390	Arbuckle	Total Depth	

Set 161 Feet (6 jts.) 8 5/8" casing
 Set 3384 Feet ~~14~~ (144 jts) 5 1/2" casing

STATE OF KANSAS)
 SS
 COUNTY OF RICE)

The undersigned certifies that to the best of his knowledge and belief the above facts are true and correct.

STAG DRILLING INC.
 BY: C. L. Curwell
 President

Subscribed and sworn to before me this 29th day of July, 1952

My Commission Expires 3/1/55

Orlando Miller
 Notary Public.

36-19-9W
 34 70

RECEIVED
 CORPORATION COMMISSION
 AUG 1 1952
 CONSERVATION DIVISION
 Wichita, Kansas