

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Rice

County. Sec. 24 Twp. 19S Rge. 9W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NW SW

Lease Owner. Carl Lebsack

Lease Name. Hoyt Well No. 1

Office Address. Hays, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-9-55 19

Application for plugging filed 6-9-55 19

Application for plugging approved 6-9-55 19

Plugging commenced 6-9-55 19

Plugging completed 6-10-55 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel E. Durkee

Producing formation Depth to top Bottom Total Depth of Well 3334 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	175	8 5/8"	casing	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 175 feet to 25 feet for each plug set.

Push first plug to 140 ft. depth cemented with 15 sacks

push second plug to a depth of 25 ft. cemented with 5 sacks cement

Name of Plugging Contractor Stag Drilling Inc. (If additional description is necessary, use BACK of this sheet)

Address Chase, Kansas Box 169

STATE OF Kansas, COUNTY OF Rice, ss.
C.L. Tyrrell

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. L. Tyrrell Pres


(Address)

SUBSCRIBED AND SWORN to before me this 16th day of August, 1955

Orlando Miller

Notary Public.

My commission expires 3/1/59



8-18-55

CONTRACTOR'S WELL LOG

Sec 24-19-9W

OPERATOR Carl Lebsack FARM NAME Hoyt WELL NO. 1Location _____ COUNTY Rice STATE KansasCOMMENCEMENT DATE 5/1/55 COMPLETION DATE 6/9/55

Log of well

SWNW SW

From	To	Formation	Deviation From Vertical
0	175	Surface Hole	
175	600	Red Bed & shale	1° -500'
600	840	Shale Shells	
840	1050	Salt	
1050	1375	Lime shale	
1375	1520	Sandy lime	
1520	1850	lime shale	
1850	2140	shale shells	
2140	2445	lime shale	
2445	2470	sandy shale	
2470	2747	lime	
2747	2887	lime shale	
2887	3215	lime	
3215	3235	lime shale	
3235	3289	congl.	
3289	3334	Simpson	
		Total Depth dry hole	

Set 175' (8 jts) 8 5/8" casing

STATE OF KANSAS)

SS

COUNTY OF RICE)

The undersigned certifies that to the best of his knowledge and belief the above facts are true and correct.

STAG DRILLING INC.,

BY: L. L. Durrell

President

Subscribed and sworn to before me this 15th day of June, 1955

My Commission Expires 3/1/59

Orlando Miller
Notary Public.

