

API NUMBER 15-175-21297-0-00

STATE OF KANSAS RECEIVED  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

LEASE NAME Davis C

JAN 17 2002

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 2  
990 Ft. from S Section Line

CONSERVATION DIVISION

990 Ft. from E Section Line

LEASE OPERATOR Oxy USA, Inc.

SEC. 16 TWP. 31 RGE. 32 (S or W)

ADDRESS 1701 N. Kansas P.O. Box 2528 Liberal, KS. 67905

COUNTY Seward

PHONE (620) 629-4200 OPERATORS LICENSE NO. 5447

Date Well Completed 5-7-93

Character of Well Gas

Plugging Commenced 12-11-01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-11-01

The plugging proposal was approved on 12-10-01 (date)

by Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Lansing Depth to Top 4798 Bottom 4832 T.D. 5900

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 3/8	1729	—
				5 1/2	5898	—

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section.  
Mixed 3 sx hulls & 25 sx cmt. to plug perfs from 4817 to 4817, mud to 1750, 45 sx 1750 to 1350, mud to 600, 80 sx cmt 600 to 0. Mixed 10 sx down 8 3/8-5 1/2 annulus from 60 to 0 & pres. up to 1000 Psl. Cut off 8 3/8 & 5 1/2 & capped 8 3/8 4 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Seward, ss.


Kenny L. Andrews (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) PO Box 2528 Liberal, KS.

SUBSCRIBED AND SWORN TO before me this 16<sup>th</sup> day of January, 2002

Anita Peterson  
Notary Public



My Commission Expires: Oct 1, 2005