

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Marko, Room 2078  
Wichita, KS 67202

SEE PLUGGING RECORD  
K.A.R.-62-3-117

API NUMBER 1517500447-0000

LEASE NAME Estelle Smith

WELL NUMBER 1

330 Ft. from <sup>N</sup> Section Line

330 Ft. from <sup>W</sup> Section Line

SEC. 22 TWP. 31 RGE. 32 <sup>W</sup>

COUNTY Seward

Date Well Completed 7-12-53

Plugging Commenced 3-20-00

Plugging Completed 3-28-00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Texaco E&P, Inc.

ADDRESS 1109 Skelly Ave Guymon, Oklahoma 73942

PHONE# (580) 338-6977 OPERATORS LICENSE NO. 4742

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/1/00 (Revised) (date)

by Gary Winters (KCC District Agent's Name).

Is ACO-1 filed? X If not, is well log attached? \_\_\_\_\_

Producing Formation Chase Depth to Top 2604 Bottom 2730 T.D. 2737

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4	707	0
				7 5/8	2618	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set

RECEIVED

See Attached Page \_\_\_\_\_ STATE CORPORATION COMMISSION

APR 11 2000

4-11-00

Name of Plugging Contractor H&K Plugging & Salvage CONSERVATION DIVISION License No. 31705  
Wichita, Kansas

Address P. O. Box 2742 Pampa, Texas 79066-2742

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Texaco E&P, Inc.

STATE OF Oklahoma COUNTY OF Texas, ss.

K. D. Austin

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 1109 Skelly Ave. Guymon, OK 73942

SUBSCRIBED AND SWORN TO before me this 10th day of April, 192000

[Signature]  
Notary Public

My Commission Expires: 4-03-04

USE ONLY ONE SIDE OF EACH FORM

**Estelle Smith #1**

**Plugging Report**

- 3/20/00 MIRU H&K Plugging (Holman Services) rig.  
Pulled 105 sucker rods. Pulled 10 jts. 2 3/8" tubing. Shut down for day.  
Called Gary Winters w/ KCC
- 3/21/00 Pumped 100 bbls. Mud, pulled 75 jts. 2 3/8" tubing. Run gauge ring to 2,554'  
Run and set CIBP @ 2,554' with 4 sks cement on top.  
Shut down due to rain.  
KCC Gary Winters on location
- 3/22-24/00 Shut down due to weather.
- 3/27/00 Pressure tested annulus with 5 sks cement to 800# pressure. Ran tubing to 730' pumped 100 bbls of mud, no circulation, pumped 170 sks cement, no circulation. Pulled tubing out of hole and shut down.
- 3/28/00 Ran tubing tagged cement at 1,209', circulated hole with 9.5# mud, pulled tubing to 730'. Pumped 75 sks cement, pulled tubing to 60', pumped 20 sks cement. Pulled tubing, cut off wellhead. Weld on steel ID plate. Clean location.

RECEIVED  
STATE CORPORATION COMMISSION

APR 11 2000

CONSERVATION DIVISION  
Wichita, Kansas