

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 1517521487-0000

LEASE NAME Estelle Smith

WELL NUMBER 22-2 76888

1320 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 22 TWP. 31S RGE. 32W (E) or (W)

COUNTY Seward

Date Well Completed _____

Plugging Commenced _____

Plugging Completed 11-8-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Texaco E&P, Inc.

ADDRESS P. O. Box 2700 Pampa, Texas 79066-2700

PHONE (806) 669-8460 OPERATORS LICENSE NO. 4742

Character of Well Gas

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-8-96 (date)

by Gary Winters, Liberal (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 2857

Show depth and thickness of all water, oil and gas formations.

11-22-96

RECORDED
INDEXED
NOV 22 1996

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	water-gas	surf.	567	8 5/8	567	0
Herrington	water - gas	2622	2632	4 1/2	2899	0
Krider	water - gas	2649	2716			
Winfield	water - gas	2726	2752			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Circulated hole with 9.5# mud, set CIBP at 2572 feet with 2 sacks cement on top, cement circulated from 617 feet to surface with 60 sacks cement, was pressured between 8 5/8 and 4 1/2 casing

Name of Plugging Contractor H & K Plugging & Salvage License No. 31705

Address P. O. Box 2742 Pampa, Texas 79066-2742

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Texaco E&P, Inc.

STATE OF Texas COUNTY OF Gray, ss.

Mark Amundson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Mark Amundson

(Address) P. O. Box 2700, Pampa, TX 79066

SUBSCRIBED AND SWORN TO before me this 20th day of November, 19 96

Sylvia L. Foster
Notary Public

My Commission Expires: 2-5-2000

USE ONLY ONE SIDE OF EACH FORM