

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-097-20, 515-

LEASE NAME Huck <sup>8000</sup>

WELL NUMBER A-1

SPOT LOCATION CNW NW

SEC. 20 TWP. 30 SRGE. 20 (W)

COUNTY Kiowa

Date Well Completed \_\_\_\_\_

Plugging Commenced 6/14/85

Plugging Completed 6/25/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR DNB Drilling

ADDRESS 535 N. Oliver, Wichita, KS 67208

PHONE # (316) 687-5471 OPERATORS LICENSE NO. 5476

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, KS

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? yes

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 5240

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	599	None
				4 1/2	5239	4464

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Plug back 5185, sand from 5185 to 5110, 4sx cement with dump bailer 5110 to 5085, Hallaburton pump 3sx hull 15sx jell, 50sx cement, 10sx jell 1sx hull, plug 150sx cement 60-40 POZ, 6% jell

Paul Luthie and Jay Kasparek on location  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corp. License No. 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104

STATE OF Kansas COUNTY OF Barber, ss.

Elmo Morgenstern (employee of operator) of (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CAREN J. McCULLOUGH  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 6-29-87

(Signature) [Signature]  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 26 day of June, 1985

My Commission expires: June 29, 1987

[Signature]  
Notary Public