


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Kiowa County. Sec. 20 Twp 30S Rge. 20W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C N/2 NE SW

Lease Owner D.N.B. Drilling, Inc.
Lease Name Trager Well No. 1
Office Address 701 First Natl. Bank Bldg., Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry

Date Well completed 8-10 1977
Application for plugging filed 8-22 1977
Application for plugging approved 8-22 1977
Plugging commenced 9-14- 1977
Plugging completed 9-20- 1977
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production
Never produced 19
Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation Depth to top 5114 Bottom 5120 Total Depth of Well 5159
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	588	None
				5 1/2	5159	2764

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of ~~plug~~ and depth placed, from feet to feet for each plug set.

Sand up to 5100'
5 sacks cement from 5100 to 5075'
Ripped at 3000' - 2900' - 2764'

Wooden Bridge at 370'
Rock from 370 to 360'
6 yards ready mix

RECEIVED
STATE CORPORATION COMMISSION

OCT 05 1977

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation, P. O. Box 187, Medicine Lodge, Ks.
671-4

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ella Priess (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Ella Priess

Suite 515 R.H. Garvey Bldg., Wichita, Ks.
67202

(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of October, 1977

My commission expires 4/30/79

Dorothy L. Schmidt
Dorothy L. Schmidt Notary Public.

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1979

DRILLERS' LOG

D N B DRILLING, INC.
 No. 1 Trager
 C N/2 NE SW, Sec. 20-30S-20W
 Kiowa Co., Kansas

Commenced: 6-22-77
 Completed: 8-10-77

Surface Casing: 569' of 8-5/8"
 cmtd w/250 sx 60-40 Pozmix, 2% gel,
 3% cc 6-22-77

FORMATIONDEPTH

Surface Hole	0 - 577
Red Bed & Shale	577 - 1185
Sand & Shale	1185 - 1910
Shale	1910 - 2233
Lime & Shale	2233 - 4935
Lime	4935 - 5065
Lime & Shale	5065 - 5160 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

DNB DRILLING, INC.

Ella Priess

Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 22nd day of August, 1977.

Dorothy L. Schmidt

Dorothy L. Schmidt, Notary Public

RECEIVED
 STATE CORPORATION COMMISSION

AUG 23 1977

CONSERVATION DIVISION
 Wichita, Kansas