

WELL PLUGGING RECORD


STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 300 Bitting Building Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Kiowa County. Sec. 20 Twp. 30S Rge. (E) 20 (W) Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines C NW SE Lease Owner Greenbrier Oil Company Lease Name Lorimar Well No. 1 Office Address 320 Central Building Wichita, Kansas Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Date well completed December 24, 1949 Application for plugging filed March 7, 1950 Application for plugging approved same (telephone) Plugging commenced March 7, 1950 Plugging completed March 12, 1950 Reason for abandonment of well or producing formation Dry Hole If a producing well is abandoned, date of last production Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well C. D. Stough - Great Bend, Ks. Producing formation None Depth to top Bottom Total Depth of Well 5160 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: None, None, None, None, 5 1/2", 5160', 3000'.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Run plug to 4000'. Run 5 sacks of cement. Mudded hole to 250'. Run 15 sacks of cement. Mudded hole to 20'. Run 10 sacks of cement. Well completed.

RECORDED MAR 29 1950 3-25-50


(If additional description is necessary, use BACK of this sheet) Correspondence regarding this well should be addressed to The R. W. Rine Drilling Co. 320 Central Building Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. E. H. Sloyer (Agent for Greenbrier) Employee of owner or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. (Signature) E. H. Sloyer 320 Central Building Wichita, Ks. (Address)

SUBSCRIBED AND SWORN to before me this 24th day of March, 19 50

R. M. Green Notary Public.

My commission expires My commission expires Dec. 29, 1952



Lorimor Well No. 1

C NW SE
 Sec. 20-30-20,
 Kiowa County, Kansas

Contractor: The R. W. Rine Drilling Company
 Started: 12/4/49 Finished: 12/24/49

Plugging Contractor: The West Supply Company - Chase, Kansas
 Started: 3/7/50 Finished: 3/12/50

Log

Sand, gravel	0- 100	
Sand, shale	100- 330	
Red bed, red rock	330- 430	
Lime	430- 460	
Red bed, red rock	460- 765	8-5/8" w/ 500 sx. @ 765'
Cement	734- 765	
Sand, shale	765-1120	
Shale, shells	1120-1500	
Lime, shells, shale	1500-1990	
Salt, shale	1990-2300	
Shale, lime	2300-2490	
Lime	2490-2935	
Lime, shale	2935-3340	
Shale	3340-3550	
Shale, lime, shale	3550-3650	
Shale, lime	3650-3710	
Sand, shale	3710-3780	
Shale, lime	3780-3950	
Shale,	3950-4020	
Shale, lime	4020-4130	
Shale	4130-4280	
Lime	4280-4905	
Lime, shale	4905-4965	
Lime	4965-5090	
Shale	5090-5158	
Chert	5158-5160	
Lime	5160-	5 1/2" w/ 250 sx. @ 5160'

State of Kansas)
 County of Sedgwick) ss

I, E. H. Sloyer, do hereby certify that the above is a true and accurate log of the Lorimor Well No. 1 located in the C NW SE of Sec. 20-30-20, Kiowa County, Kansas.

E. H. Sloyer
 Secretary

Sworn to and subscribed before me this 24th day of March, 1950.

My commission expires Dec. 29, 1952

R. M. Green
 Notary Public

