

Give All Information Completely
Make Required Appointment
Mail or Deliver Request
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Name of Conservation Agent who supervised plugging of this well..... C. D. Stough.....
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3450 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Filled with heavy mud to 240'. Plug and 15 sacks cement. Filled with mud to 30'. Plug and 10 sacks cement.

~~JUN 2 - 1948~~

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....**B. & R. Drilling, Inc.**
Address.....**Russell, Kansas**

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. L. Roberts (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of May 1948

My comomission expires

6/17/50 **PLUGGING**
FILE SEC 36 T 20 R ¹²⁷⁶
BOOK PAGE 31 LINE 37

9-45-6M

.....
Notary Public.

15.009.00777.0000

Dannebohm
B & R Drilling, Inc.

Sec. 36 Twp. 20 Rge. 12W
County: Barton, Kansas

Total Depth: 3450'
Comm: 5/9/48 Comp; 5/23/48

Top Brown Lime - 3149
Top Lansing K.C. - 3164
Top Simpson Shale - 3399
Top Arbuckle Chert - 3413
Top Arbuckle Dolomite - 3420'

Casing
13 Jts. 8 5/8" Set @ 242'

Cement
210 Sx - Circulated

Formation:	Depth:
Sand	20
Clay	30
Sand	40
Sand & Shale	230
Red Bed	242
Red Bed & Shells	346
Red Rock	562
Red Bed & Shells	5.95
Anhydrite	625
Shael & Shells	995
Shale, Brokwn Lime, Shells	1115
Shale & Salt	1362
Shale & Lime Shells	1398
Anhydrite & Shale	1450
Anydrite	1460
Shale & Lime	1745
Lime	1785
Sandy Lime & Shale	1810
Sime & Shael	1875
Lime	1950
Lime & Shale	2005
Broken Lime & Shael	2105
Lime & Shale	2330
Broken Lime & Shale	2440
Lime & Shale	2725
Shale Sandy	2772
Lime	2850
Lime & Shale	2985
Lime & Shale	3175
Lime	3205
Lime & Shale	3380
Conglomerate	3390
Lime & Shale	3400
Shale	3413
Arbuckle Lime	3425
Lime	3450

STATE OF KANSAS)

) SS

RUSSELL COUNTY)

I hereby certify that the above information is true and correct
to the best of my knowledge.

Subscribed and sworn to before me this 29th day of May, 1948.

My Comm. Expires 6/17/50

FILE SEC 36 T 20 R 12W
BOOK PAGE 31 LINE 37

Notary Public