

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

BARTON County. Sec. 36 Twp. 20 Rge. 12 (X) W (W)

Location as "NE/CNW/SW" or footage from lines NE SE SW

Lease Owner PETROLEUM, INC.

Lease Name DANNEBOHM Well No. 14

Office Address ROUTE 2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed OCTOBER 21, 19 57

Application for plugging filed OCTOBER 22, 19 57

Application for plugging approved OCTOBER 21, 19 57

Plugging commenced OCTOBER 21, 19 57

Plugging completed OCTOBER 21, 19 57

Reason for abandonment of well or producing formation  
No Produccible Zones

If a producing well is abandoned, date of last production None 19    

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives, Box 8, Pratt, Kansas

Producing formation ----- Depth to top --- Bottom --- Total Depth of Well 3445' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	248'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet for each plug set.

Mud up with heavy mud to 245' pushed down 1/3 sack hulls at 245' followed by wooden plug. Placed 20 sacks cement through drill pipe on to plug. Mud up to 35' and placed 1/3 sack hulls at 35' followed by wooden plug and 10 sacks cement to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY

Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.

Don Searle (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

Route 2, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 30 th day of October, 19 57

[Signature]  
Notary Public.

My commission expires July 11, 1960

PLUGGING  
FILE SEC 36 T 20 R 124  
BOOK PAGE 56 LINE 13

RECEIVED  
NOV 2 1957  
WICHITA, KANSAS

# WELL LOG

15.009.05712.0000

COMPANY PETROLEUM, INCORPORATED

SEC. 36 T. 20S R. 12W

FARM DANNEBOHM

NO. 14

LOC. NE, SE, SW


TOTAL DEPTH 3445'

COUNTY BARTON CO., KANSAS

COMM. October 14, 1957

COMP. October 21, 1957

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 248' W/225 sax.

ELEVATION 1833' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

250	Surface soil & sand
850	Shale & shells'
1430	Shale & salt
1745	Shale & lime
2075	Lime
2958	Shale & lime
3155	Lime
3233	Lime & shale
3399	Lime
3445	Lime & chert
3445	T. D.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 2 1957

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 36 T. 20 R. 12W  
BOOK PAGE 56 LINE 13

State of KANSAS }  
County of BARTON } ss:

I, Verne A. Morris of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the DANNEBOHM #14 well

Verne A. Morris

Subscribed and sworn to before me this 29th day of October 19 57

My Commission Expires: July 11, 1960

Deed T. Brown  
NOTARY PUBLIC