

15.009.02016.0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barton SEC. 36 TWP. 20 RGE. 12 K/W
Location as in quarters or footage from lines:
NW/SE/SW

Locate Well
correctly on above
Section Platt.

Lease Owner Petroleum, Inc.
Lease Name Dannebohm Well No. #10
Office Address Box 1447 - Great Bend, Ks. 67530
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed _____
Application for plugging filed _____
Plugging commenced May 25, 1983
Plugging completed June 01, 1983
Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
Producing formation _____ Depth to top _____ bottom _____ T.D. 3426'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	260'	NONE
				5 1/2"	3433'	324.19'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Dumped five (5) sacks cement, sanded to 3335' and dumped
five (5) sacks cement.
Pulled ten (10) joints 5 1/2" casing.
Squeezed well with four (4) sacks hulls, twelve sacks gel,
sixty-five (65) sacks cement, three (3) sacks gel, one (1) sack
hulls, released plug and pumped one hundred (100) sacks 50/50
pozmix cement with 4% added and 3% calcium chloride,
500# max. press, 200 psi shutin.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
JAMES W. ROCKHOLD / Box 698 - Great Bend, Ks.
(Address) 67530

SUBSCRIBED AND SWORN TO before me this 29th day of June, 1983



My Commission expires _____

Margaret Prosser
Notary Public.
RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1983

15.009.02016.0000

36-20-12W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PETROLEUM, INC.
Farm- Dannebohm No. 10

SEC. 36 T. 20 R. 12W
NW SE SW
1600' fr WL, 990' fr SL

Total Depth. 3435
Comm. 7-9-55 Corp. 7-18-55
Shot or Treated.
Contractor. Garvey Drilling Co.
Issued. 10-15-55

County Barton
KANSAS



CASING:
8 5/8 @ 260' w/ 200 sx cmt.
5 1/2 @ 3433' w/ 50 sx cmt.

Elevation. 1820 DF

Production. 700 BOPD

Figures indicate Bottom of Formations.

sand	200
red bed	578
anhydrite	605
shale, shells & sand	1060
shale & salt	1150
shale & shells	1250
shale	1500
lime & shale	2300
shale	2510
shale & lime	2900
lime	2978
lime & shale	3237
lime	3380
Arbuckle	3435
Total Depth	

TOPS:	
Heebner	3001
Toronto	3016
Douglas sand	3032
Brown lime	3133
Lansing	3144
Arbuckle	3373

RECEIVED
STATE CORPORATION COMMISSION

MAY 09 1983

CONSERVATION DIVISION
Wichita, Kansas