

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.009.00730.0000

API NUMBER Comp 11-21-53

LEASE NAME Dannebohm

WELL NUMBER #1

SPOT LOCATION SW SW SW

SEC 36 TWP 20 RGE 12 (#) or (W)

COUNTY Barton

Date Well Completed 11-21-53

Plugging Commenced 7-19-84

Plugging Completed 7-25-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Inc.

ADDRESS Box 1447, Great Bend, Ks. 67530

PHONE # (793)-8968 OPERATORS LICENSE NO. 5238

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? 6

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3435'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	250'	None
				4-1/2"	3433'	341.31'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Dumped 4 sacks cement on bottom. Sanded back to 3230' and dumped 4 sacks cement. Shot casing at 3000', 2800', 2600, and 2400'. Casing pulled in two at 341'. Pulled 11 joints of 4-1/2" casing. Squeeze well with 4 sacks hulls, 25 sacks cement, 9 sacks gel, 40 sacks cement, 3 sacks gel, 1 sack hulls, released plug and pumped 100 sacks 50/50 pozmix cement with 6% added gel and 3% calcium chloride. Maximum pressure was 800 psi and shutin 300 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED

STATE CORPORATION COMMISSION

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

AUG 01 1984

SUBSCRIBED AND SWORN TO before me this 31st day of July, 1984

CONSERVATION DIVISION
Wichita, Kansas

My Commission expires: _____

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
Notary Public