


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plot

33  
Barton County, Sec. 30 Twp. 20 Rge. 14 (E) (W)  
Location as "NE/CNW4SW4" or footage from lines NW NE SE  
Lease Owner National Cooperative Refinery Assn.  
Lease Name McGreevy B-6 Well No. \_\_\_\_\_  
Office Address Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 7/22/76 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 7/24/76 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4057 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	845	none
				5 1/2"	3868	1365

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Squeezed bottom hole with 100 sacks cement, pumped plug to 1412'.  
Shot pipe at 1357', pulled 44 joints. Mudded to 315', set 10'  
rock bridge from 315 to 300' and filled hole with 4 1/2 yards ready  
mix from 300 to base of cellar.

PLUGGING COMPLETE.

7-28-76

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS

Subscribed and sworn to before me this 26th day of July, 1976

Margaret Melcher  
Notary Public.

My commission expires \_\_\_\_\_



COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- NATIONAL COOPERATIVE REFG. ASSOC.  
Farm- McGreevey "B" No. 6

SEC. 33 T. 20 R. 14W  
NW NE SE

Total Depth. 3922  
Comm. 6-26-52 Comp. 7-17-52  
Shot or Treated.  
Contractor. John Lindas Oil, Inc.  
Issued. 9-6-52

County Barton  
KANSAS



Elevation. 1912 DE

Production. SWDVI

CASING:

8 5/8" 315' com. w/350 sx  
5 1/2" 3868' com. w/200 sx

Figures Indicate Bottom of Formations.

soil, sand	60
sand & shale	200
shale	270
sand & shale	395
sand	435
sand & red bed	470
shale, shells & red bed	615
red bed	675
red bed & shale	830
anhydrite	865
red bed & shale	1070
shale	1145
shale & shells	1770
lime & shale	2310
lime	2480
shale & lime	2980
lime	3231
sand & shale	3239
lime & shale	3304
lime	3594
arbutle lime	3596
lime	3922
Total Depth	

Scout Tops:

Anhydrite	830
Heebner	3198
Toronto	3218
Douglas	3230
Brown Lime	3304
Lansing	3314
Simpson	3557
Arbutle	3591

RECEIVED  
STATE GEOLOGICAL COMMISSION

APR 13 1976

WELL LOG BUREAU  
Wichita, Kansas