

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15.009.02066.0000

LEASE NAME McGreevy

WELL NUMBER B-8

SPOT LOCATION NE SW SE

SEC. 33 TWP. 20 RGE. 14W (E) or (W)

COUNTY Barton

Date Well Completed \_\_\_\_\_

Plugging Commenced 10-2-86

Plugging Completed 10-10-86

LEASE OPERATOR National Cooperative Refinery Association

ADDRESS P.O. Box 6 Great Bend, Kansas 67530

PHONE # (316) 793-7824 OPERATORS LICENSE NO. 5565

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3550'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	832'	none
				5-1/2"	3548'	2476'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3250' and 5 sacks cement. Shot pipe @2714', 2476', pulled a total of 77 joints of 5-1/2" casing. Plugged surface with 5 hulls and 100 sks. econolite.  
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.


Mike Kelso, Vice-President (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347 Chase, Ks. 67524

OCT 30 1986

SUBSCRIBED AND SWORN TO before me this 28 day of October, 19 86



My Commission expires: \_\_\_\_\_

Irene Hoover  
Notary Public

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
 508 East Muddock, Wichita, Kansas


COPY

15.009.02066.0000

Company. NATIONAL COOPERATIVE REFINERY ASS'N SEC. 33 T. 20 R14W  
 Farm. McGreevy "B" No. 8 NE/4 SW/4 SE/4

Total Depth. 3552  
 Comm. 11-18-52 Comp. 12-2-52  
 Shot or Treated.  
 Contractor, Birmingham-Bartlett Drilling Co.  
 Issued. 1-3-53

County Barton  
 KANSAS



**K. G. S. LIBRARY**

CASING:

8-5/8 set at 632 w/ 425 sx cement  
 5-1/2 set at 3548 w/ 125 sx cement

Elevation. 1912

Production. 1257 bbls. no wtr.

Figures in feet. Bottom of Formations.

TOPS-SCOUT

clay & sand	160		
shale & shells	270	Anhydrite	823
sand	360	Heebner	3178
red bed	823	Brown lime	3279
anhydrite	850	Lansing	3288
shale & shells	1625	Base KC	3484
lime & shale	1720	Conglomerate	3515
broken lime	2110	Sand	3531
shale & shells	2850	Arbuckle	3547
shale & lime	3110		
lime	3160		
lime & shale	3279		
lime	3539		
shale & lime	3552	T. D.	

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 25 1986  
 CONSERVATION DIVISION  
 Wichita, Kansas