

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.009-02065.0000

LEASE NAME McGreevy

WELL NUMBER B-7

SPOT LOCATION NW SW SE

SEC. 33 TWP 20 RGE 14W (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 10-7-86

Plugging Completed 10-10-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR National Cooperative Refinery Association

ADDRESS P.O. Box 6 Great Bend, Kansas 67530

PHONE # (316) 793-7824 OPERATORS LICENSE NO. 5565

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3545'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	835'	none
				5-1/2"	3543'	1976'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3300' and 5 sacks cement. Shot pipe @2508', 2314', 2100', 1976', pulled a total of 63 joints of 5-1/2" casing. Plugged surface with 5 hulls and 100 sks. econolite.

Plugging Complete.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524


STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

10-30-86 (Signature) Mike Kelso

Box 347 Chase, Ks. 67524 (Address)

SUBSCRIBED AND SWORN TO before me this 28 day of October, 1986



Irene Hoover
Notary Public

My Commission expires: _____

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY

Company- NATIONAL COOPERATIVE REFINERY ASSOC.
Farm- McGreevy "B" No. 7

SEC. 33 T. 20 R. 11W
NW SW SE


Total Depth. 3545
Comm. 10-2-52

Comp. 10-16-52

County Barton
KANSAS

Shot or Treated.

Contractor. Lewis Drilling Company
issued. 12-6-52



CASING:

8 5/8" 835'

K. G. S. BUREAU

Elevation. 1911

Production. 805 BO & MW

Figures Indicate Bottom of Formations.

sand	200
shale blue	255
red bed	828
anhydrite	835
shale	1370
shale, shells & salt	1640
shale & lime	1795
shale & shells	1820
lime broken	1940
lime	2140
lime & shale	2400
shale	2475
shale & lime	3020
lime	3202
shale & lime	3285
lime	3445
lime & shale	3470
lime	3510
lime & shale	3530
shale & sand	3540
lime	3545
Total Depth	

Scout Tops:

Heebner	3175
Toronto	3190
Douglas	3211
Brown Lime	3274
Lansing	3284
Arbuckle	3542

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1986
CONSERVATION DIVISION
Wichita, Kansas