

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 6-5-51

15.009.02060.0000

LEASE NAME McGreevy "B"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

SPOT LOCATION SW SW SE

SEC. 33 TWP. 20 RGE. 14 (XXor) (W)

LEASE OPERATOR National Cooperative Refinery Association

COUNTY Barton

ADDRESS Box 6, Great Bend, Kansas 67530

Date Well Completed 6-5-51

PHONE # (316) 793-7824 OPERATORS LICENSE NO. 5565

Plugging Commenced 5-6-85

Character of Well Inj.
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-6-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Marion Schmidt, Hays, Ks.

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 3566'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	831'	-0-
				5 1/2	3560'	623'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Allied Cementing Company cemented w/500 sx 50/50 Pozmix - 4% Gel - 3% CaCl. and 1/4# Cello Flake per sx. & 600# hulls. 500# Max. Press. Complete @ 2:15 p.m. 5-6-85

(If additional description is necessary, use BACK of this form.)

RECEIVED

STATE CORPORATION COMMISSION

Name of Plugging Contractor None License No. _____

Address _____

MAY 10 1985

CONSERVATION DIVISION


Wichita, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.

I. J. Gotsche (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
I. J. Gotsche
(Address) Box 6, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 9th day of May, 1985



Patricia Schultz
Notary Public

My Commission expires: January 29, 1989

WELL OWNER: Tom Palmer
CONTRACTOR: The Palmer Oil Corporation

Location: SW SW SW
Section 33-23-14N
Darton County, Kansas
Elevation: 1917 R.B.

Commenced: 5/8/51
Completed: 5/21/51 (Rotary)
Completed: 5/5/51 (Cable Tools)
RESULTS: 2186 Bbls. (Depthograph)

Casing Record

8 5/8" - 831' cemented 400 sacks
5 1/2" - 3560' cemented 90 sacks

Shale & sand	0	224
Shale	224	310
Sand	310	355
Shale, sand & red bed	355	525
Shale	525	822
Anhydrite	822	853
Shale	853	1575
Shale & shells	1575	1780
Shale & lime	1780	2115
Lime & shale	2115	2922
Lime	2922	3150
Lime & shale	3150	3284
Lime	3284	3486
Lime & shale	3486	3520
Lime	3520	3560
Arbuckle Lime	3560	3566 TD

FORMATION TOPS (R. B.)

Heebner	3177
Brown lime	3279
Lansing	3291
Arbuckle	3560

Drill Stem Test #1 - 3294-3328, tool open 30 minutes. Recovered 65' oil and gas cut mud.

Drill Stem Test #2 - 3410-3454, tool open 30 minutes. Recovered 180' heavily oil and gas cut mud and 30' of free oil.

Acidized with 500 gallons on 6/7/51. Acidized with 1000 gallons on 6/8/51.

TOM PALMER

By A. H. Smith

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me, a Notary Public in said county and state this 15th day of June, 1951.

Olaf M. Kelling
Notary Public

My commission expires: 9/30/53.

RECEIVED
STATE CORPORATION COMMISSION

MAY 10 1985

CONSERVATION DIVISION
Wichita, Kansas