

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Berexco, Inc.

SEC. 33 TWP. 20 RGE. 14W (S) or (W)

ADDRESS Box 723 Hays, Kansas 67601

COUNTY Barton

PHONE#(316) 628-6101 OPERATORS LICENSE NO. 5363

Date Well Completed

Character of Well Oil

Plugging Commenced 8-26-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-29-94

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3568'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	817'	none
				5 1/2"	3566'	2585.60

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 3500', ran 5 sacks cement. Shot pipe @2600'. Pulled to 1650' pumped 110 sacks cement 200# hulls, pulled to 850' pumped 40 sacks 100# hulls, pulled to 430' circulated to surface 60/40 10% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 2 day of September

Irene Herzberg
 Notary Public

My Commission Expires:



Revised 05/88