

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barton County. Sec. 33 Twp. 20S Rge. (E) 11 (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines C-SW SW NE

Lease Owner Sunray Oil Corporation

Lease Name U. B. McGreevy Well No. 3

Office Address Box 195, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-28 19.52

Application for plugging filed 3-31 19.52

Application for plugging approved 3-31 19.52

Plugging commenced 3-28-19.52

Plugging completed 3-28 19.52

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3600 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lansing	Dry	3307'		8-5/8"	8 1/4'	None
Arbuckle	Dry	3593'	3600'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole to 270'. Set plug at 270' with 20 sax cement on plug. Mudded hole to 35'. Set plug at 35' w/10 sax cement on top to complete plugging.

APR 18 1952

4-3-52

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mouser Drilling Co.

Address Wichita, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

W. E. Westbrook, Jr. (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W. E. Westbrook, Jr. Jr. Engr.

Box 195, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 1952

Notary Public

My commission expires April 19, 1952



McGreevy #3 Well

Sec. 33-20S-14W, Barton County, Kansas

Drilled for: Sunray Oil Corporation

Drilled by: Mouser Drilling Company

Drilling Commenced: March 15, 1952

Drilling Completed: March 28, 1952

Casing Record

8 5/8" 845' 2 1/4" 8 rd thd


<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION</u>	<u>DEPTH</u>
Cellar	5		
Sand	235		
Shale	310		
Sand	360		
Red bed	420		
Sand	455		
Red bed & shells	680		
Shale & shells	832		
Anhydrite	845		
Reamed to 13 3/4" hole			
Cement	800-845		
Anhydrite	860		
Shale & shells	1335		
Salt	1500		
Shale & shells	1700		
Lime & shale	1870		
Shale & lime	2260		
Lime & shale	2550		
Shale	2420		
Shale & lime	2960		
Lime	3225		
Shale	3299		
Broken lime	3300		
Lime	3515		
Lime & shale	3550		
Sand	3559		
Sand & shale	3583		
Shale	3593		
Arbuckle	3600		
Total Depth	3600'		

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above and within statement is a true and correct record and log of the well drilled on the above described location to the best of my knowledge and belief.

B. H. Mouser

Subscribed and sworn to before me this 16th day of April 1952.



Frances L. Walker
Notary Public

My Commission Expires:

March 18, 1954