


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 33 Twp. 20 Rge. 14 (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines C-NE SE NE
Lease Owner Sunray Oil Corporation
Lease Name E. McGreevy Well No. 2
Office Address Box 195, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-23 19 52
Application for plugging filed 2-25 19 52
Application for plugging approved 2-26 19 52
Plugging commenced 2-23 19 52
Plugging completed 2-23 19 52
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Harold J. Hollis
Producing formation None Depth to top Bottom Total Depth of Well 3640 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lsg-KC	Dry	3001		8-5/8"	834'	None
Simpson Sand	Water	3548				
Arbuckle	Dry	3584	3640			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole to 275'. Set plug at 275' w/15 sax cement on ~~XXX~~ plug. Mudded to 40'. Set plug with 1/2 sax Hulls on top. Dumped 10 sax cement on top to complete plugging.

Plugging Contractor: Mouser Drilling Co. Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Sunray Oil Corporation
Address Box 195, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
W. E. Westbrook, Jr. (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W. E. Westbrook, Jr. Jr. Engineer
Box 195, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of February, 1952

Martha Scott

Notary Public.

My commission expires April 19, 1952.



U. B. McGreevy No. 2 Well
 Sec. 33-208-11W, Barton County, Kansas

Drilled for: Sunray Oil Corporation
 Drilled by: Mouser Drilling Company

Drilling Commenced: February 7, 1952
 Drilling Completed: February 23, 1952

Casing Record

8 5/8" 83 1/2" 8 rd thd 2 1/4" Casing

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION</u>	<u>DEPTH</u>
Cellar	5		
Sand	230		
Shale	300		
Sand	370		
Red Bed & Sand	415		
Sand	465		
Red Bed & Shale	650		
Red Bed	825		
Anhydrite	835		
Reaming to 13 3/4" Hole			
Anhydrite	850		
Shale & Lime	1815		
Lime	1965		
Lime & Sand	2030		
Lime & Shale	2185		
Shale	2235		
Lime & Shale	2410		
Shale & Shells	2560		
Shale	2670		
Shale and Lime	2815		
Lime	2895		
Lime & Shale	2955		
Lime	3211		
Lime & Shale	3220		
Shale	3292		
Lime	3559		
Simpson Sand	3548-3559'		
Sand & Shale	3575		
Shale	3581		
Arbuckle	3640		
Total Depth - Dry Hole	3640'		

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above and within statement is a true and correct record and log of the well drilled on the above described location to the best of my knowledge and belief.

B. H. Mouser

Subscribed and sworn to before me this 27th day of February 1952.

Frances L. Webber
 Notary Public

My Commission Expires:
March 18, 1954

