

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-21120-0000

LEASE NAME Garfield #1

WELL NUMBER _____

SPOT LOCATION C N/2 N/2 SE

SEC. 8 TWP. 23 RGE. 17W (E) or (W)

COUNTY Pawnee

Date Well Completed _____

Plugging Commenced 1/2/85

Plugging Completed 1/16/85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kelso Casing bought f/ Mustang Drilling

ADDRESS S. Hwy 281, Box 1609, Great Bend, Ks. 67530

PHONE # (316) 792-7323 OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	459'	none
				5 1/2"	4399'	2975'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 4150' & 5 sacks cement. Shot pipe at 3504', 3300', 3105' and 2975'. Pulled 74 joints of pipe. Plugged well with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug, & 125 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling

License No. 6050

Address Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss. JAN 18 1985

R. Darrell Kelso

(employee of operator) CONSERVATION DIVISION

(operator) of above-described well, being first duly sworn on oath, says: That Wichita, Kansas

I have knowledge of the facts, statements, and matters herein contained and


the log of the above-described well as filed that the same are true and

correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 17th day of January, 19 85



My Commission expires: _____

Irene Hoover
Notary Public

WAYNE DOBBS, INC.

TELEPHONE (316) 793-3282

P. O. BOX 315

GREAT BEND, KANSAS 67530

*Nancy
murphy
Alma,*

file
15-145-21120-0000

CASING RECORD

Mustang Drilling & Exploration, Inc.
agent for Alma, Inc.
Drawer 1609
Great Bend, Kansas 67530

RE: Garfield # 1
C N/2 N/2 SE
Sec. 8 T23 R17W
Pawnee County, Ks.

854-459-325 ref

DATE: April 21, 1984

TOTAL DEPTH: 4400'

DEPTH PIPE SET: 4399' (or 1' off bottom)

CASING: 109 joints new 14# 5 1/2" casing tally 4421.65' thds off

SHOE JOINT: 41.10' overall including guide shoe

CEMENT: 20 bbl. Salt Flush + 500 gal. Mud Flush + 75 sacks
60/40 Posmix + 75 sacks 60/40 Posmix with gilsonite
with all cement having 18% Salt & 3/4th of 1% of
CFR2

CENTRALIZERS: 4181'---4232'---4315'---4358'

ZERO POINT: 5' above ground level

PLUG DOWN: 11:55 p.m.

COMMENT: Lost circulation while pumping plug down at approx.
2200'. Slowed pump down to 3 bbl. per min. and
regained full circulation with plug at approx. 3500'.
Retained full circulation while pumping plug rest
of way to bottom while pumping 5 bbl. per min.

650' CEMENT 3 1/2" IP

am top 3540

Wayne Dobbs
Wayne Dobbs

RECEIVED
STATE CORPORATION COMMISSION

JAN 09 1985

CONSERVATION DIVISION
Wichita, Kansas

*1st CORNER
GARFIELD AS OF BRIDGE
1 1/2" E
3/4" S
W 1/4 N 70*