

15,145-00984-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 6 Twp. 23 Rge. 17 (E) (W)

Location as "NE/CNW/SW" or footage from lines C E/2 SE SW
Lease Owner National Cooperative Refinery Association
Lease Name Wolcott Well No. 1
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed October 16 19 54
Application for plugging filed October 19 19 54
Application for plugging approved October 20 19 54
Plugging commenced October 16 19 54
Plugging completed October 16 19 54
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4372 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	345'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Mudded hole from 4372 to 300'. Set plug at 300' with 1/2 sack of hulls and 20 sacks of cement. Set plug at 35' with 10 sacks of cement, filling up to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Thunderbird Drilling Company
Address 1311 Union National Bank Building, Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Seas
305 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of October, 19 54

My commission expires June 30, 1958
C. Orville May Notary Public.



10-22-54

15-445-00984-0000

N.C.R.N.

WOLCOTT #1

COMMENCED: September 30, 1954
 COMPLETED: October 16, 1954

CONTRACTOR: Thunderbird Drilling, Inc.
 1311 Union Nat'l Bank Bldg.
 Wichita, Kansas

LOCATION: C E/2 SE/4 SW/4 -
 Sec. 6, 23.S, 17.W -
 Pawnee County, Kansas.

SURFACE CASING: 345' 8 5/8" Casing cemented
 with 225 sacks cement, 2 sacks
 Calcium Chloride

OIL STRING: None

WELL LOG

0	-	50	Sand
50	-	85	Clay
85	-	115	Redbed
115	-	165	Sand
165	-	270	Shale
270	-	290	Sand
290	-	345	Shale and shells
345	-	375	Shale and redbed
375	-	655	Sand
655	-	1125	Redbed
1125	-	1150	Anhydrite
1150	-	2095	Shale and shells
2095	-	2230	Shale and lime
2230	-	2530	Lime
2530	-	2635	Brown Lime
2635	-	2730	Shale and lime
2730	-	3160	Shale and shells
3160	-	3255	Shale and lime
3255	-	3540	Lime
3540	-	3717	Shale and lime
3717	-	3770	Shale
3770	-	4105	Lime
4105	-	4210	Lime and shale
4210	-	4252	Shale
4252	-	4305	Shale and chert
4305	-	4330	Chert Lime
4330	-	4350	Chert and shale
4350	-	4353	Shale
4353	-	4372	Viola Lime
4372	-		Rotary Total Depth

The undersigned, Charles W. Aikins, Jr., an officer of Thunderbird Drilling, Inc., hereby certifies that the above is a true and correct log of the formations encountered in the drilling of the #1 Wolcott well as shown in the daily drilling reports.

THUNDERBIRD DRILLING, INC.

Charles W. Aikins, Jr.
 Charles W. Aikins, Jr., Pres.

Subscribed and sworn to before
 me this 18th day of October, 1954.

Leta Helen
 Notary Public

My Commission Expires:
 August 25, 1956

