

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barton SEC. 27 TWP. 20S RGE. 12W E/W
Location as in quarters or footage from lines:
SW SW NW

Locate Well
correctly on above
Section Platt.

Lease Owner Southern States Oil Company
Lease Name Churchill B-2 Well No. _____
Office Address P.O. Box 1365 Great Bend, Ks. 67530
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 10-19-82
Plugging completed 10-27-82
Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
Producing formation _____ Depth to top _____ bottom _____ T.D. 3412'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				10-3/4"	272'	none
				7"	3411'	1599'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom, ran 5 sacks cement, sanded to 3150' and ran 5 more sacks
cement. Shot casing @2817', 2699', 2583', 2468', 2202', 2004', 1806', 1690',
1578', pulled a total of 49 joints of 7" casing. Plugged well with 25 sacks
cement, 4 sacks hulls, 12 sacks gel, 70 sacks cement, 3 sacks gel, 1 sack hulls,
8-5/8" plug, 70 sacks cement, 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of October, 1982

My Commission expires:



Irene Hogver
RECEIVED
Notary Public.
STATE CORPORATION COMMISSION

NOV 1 1982

CONSERVATION DIVISION
Wichita, Kansas

11-1-1982

15.009.04949.0000

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: 7-6-53

Contractor: Quaker Drilling Co., Inc.

Completed: 7-16-53

Churchill No. B-2

Elevation: 1836 R.B.

SW SW NW Sec. 27-20S-12W

Barton County, Kansas

Production:

Casing Record:

Set 272' of 10 3/4" w/ 25 sacks cement

Set 3412' of 7" w/ 100 sacks cement

(Figures Indicate Bottom of Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>
Sand	200	Anhydrite 610
Shale & Shells	250	Heebner 3021 -1185
Red Bed & Shale	610	Br. Lansing 3146 -1310
Anhydrite	640	Lansing 3163 -1327
Shale & Shells	800	Conglomerate 3388 -1552
Red Bed & Shale	1180	Arbuckle 3397 -1561
Shale	1425	
Lime & Shale	1575	Total Depth (R) 3412'
Lime	1675	
Lime & Shale	2055	
Shale & Shells	2310	
Lime & Shale	2955	
Lime	3010	
Lime & Shale	3190	
Lime	3255	
Lime & Shale	3300	
Lime	3375	
Lime & Shale	3412	