

15.009.15638.0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Barton County, Sec. 27 Twp. 20 Rge. 12 (E) (W) X

Location as "NE/CNWSW" or footage from lines C S/2 SW SW  
Lease Owner National Cooperative Refining Assoc.  
Lease Name Bryant Well No. #6  
Office Address Box 6, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 1-4-74 19  
Plugging completed 1-10-74 19  
Reason for abandonment of well or producing formation  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation Depth to top Bottom Total Depth of Well 3476 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3475'	2411.31'
				8 5/8"	296'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.  
Made bottom hole plug back with sand to 3390'  
Mixed and 5 sacks cement thru dump bailer  
Plugged hole with 2 sacks hulls - 20 sacks gel and 100 sacks cement


RECEIVED  
STATE CORPORATION COMMISSION  
JAN 14 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
1-14-1974

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Co.  
Address Box 364 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Lessard Sec.  
Box 364 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 12 day of January, 1974.  
Sidney D. Miller  
Notary Public.



My commission expires 12/22/1976

# WELL LOG

*Boyd*  
*Drill*

COMPANY National Cooperative Refinery Association  
FARM Bryant NO. 6

SEC. 27 T. 20S R. 12W  
LOC. 9/8 1/2 SW 1/4 SW 1/4

TOTAL DEPTH 3176  
COMM. 9-3-58 COMP. 9-23-58  
SHOT OR TREATED  
CONTRACTOR Lowie Drilling Company  
ISSUED

COUNTY Barber  
KANSAS


CASING

20	10
15	At 8 5/8" = 299'
12	6
13	At 5 1/2" = 3175'

ELEVATION 1836' KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 0 - 190 Sand
- 190 - 275 Brown Shale & Sand
- 275 - 325 Red Bed
- 325 - 619 Shale & Shells
- 619 - 655 Anhydrite
- 655 - 1600 Shale & Shells
- 1600 - 2005 Shale & Lime
- 2005 - 2850 Shale & Lime Streaks
- 2850 - 2890 Lime
- 2890 - 3225 Lime & Shale
- 3225 - 3105 Lime
- 3105 - 3131 Arbuckle
- 3131 - 3176 Lime
- 3176 - Total Depth

- Geologic Top
- Horton 3021'
  - Wacato 3040'
  - Douglas 3055'
  - Brown Lime 3131'
  - Lansing 3165'
  - Arbuckle 3105'

**RECEIVED**  
STATE CORPORATION COMMISSION  
NOV 8 1973  
CONSERVATION DIVISION  
Wichita, Kansas