


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County, Sec. 27 Twp. 20S Rge. 12W (E) (W)
Location as "NE/CNW%SW%" or footage from lines SW SE NW
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name CHURCHILL Well No. B-6
Office Address 800 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil well
Date well completed October 23, 1958 19
Application for plugging filed November 10, 1959 19
Application for plugging approved November 12, 1959 19
Plugging commenced November 19, 1959 19
Plugging completed November 23, 1959 19
Reason for abandonment of well or producing formation non-productive in commercial quantities
If a producing well is abandoned, date of last production November 8, 1959 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation Arbuckle Depth to top 33418 Bottom Total Depth of Well 3440 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	275	Cemented
				5 1/2"	3430	2802'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand	3430 to 3420
Cement	3420 to 3380
Mud	3380 to 275
Rock	275 to 265
Cement	265 to 190
Mud	190 to 40
Rick Rock	40 to 30
Cement	30 to 0

RECEIVED
STATE CORPORATION COMMISSION

DEC 8 1959

CONSERVATION DIVISION
Wichita, Kansas

12-8-1959

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn & Smith Pipe Pulling Company
Address Box 114 - Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dwight J. Wilson
800 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 59

My commission expires August 10, 1961
Benjamin M. Mandell Notary Public.

P

15.009.04953.0000

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: October 5, 1958

Contractor: Quaker Drilling Co., Inc.

Completed: October 16, 1958

Churchill No. 6-D
SW SW NW Section 27-20S-12W
Barton County, Kansas

Elevation: 1843 K. B.

Casing Record

Set 3 5/8 inch casing at 275 feet with 250 sacks cement
Set 5 1/2 inch casing at 3430 feet with 125 sacks cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil & Sand	220	Neobner	3031 -1188
Shale	275	Brown Lime	3156 -1313
Shale and Shells	300	Lansing	3173 -1330
Red Bed	615	Base of Kansas City	3402 -1559
Anhydrite	645	Arbuckle	3418 -1575
Shale and Shells	885	Rotary Total Depth	3440 -1597
Shale, Shells with Salt	1430		
Sandy Lime	1599		
Lime and Shale	1845		
Sandy Lime and Shale	2000		
Lime and Shale	2215		
Shale	2540		
Lime and Shale	2880		
Lime - Broken	2936		
Lime and Shale	3300		
Lime	3355		
Lime and Shale	3419		
Dolomite	3440		

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 1959
CONSERVATION DIVISION
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well drilled in the SW SE NW of Section 27, Township 20 South, Range 12 West, Barton County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. McCaul
Thomas M. McCaul, President

SUBSCRIBED AND SWORN TO BEFORE ME a Notary Public this 22nd day of October, 1958.

Virginia Mendell
Virginia Mendell, Notary Public

MY COMMISSION EXPIRES:
August 10, 1961