

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.009.02052.0000

API NUMBER Drilled 1954

LEASE NAME Bondurant

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 26 TWP. 20SRGE. 14W(E)or(W)

COUNTY Barton

Date Well Completed

Plugging Commenced 5-2-97

Plugging Completed 5-5-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR J. R. Oil Productions

ADDRESS P. O. Box 942 Great Bend, KS 67530

PHONE#(316) 792-6077 OPERATORS LICENSE NO. 30765

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filled? if not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3540'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	467'	none
				4 1/2	3528'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from feet to feet each side. Perforated well at 1650, 815 and 425. Ran 61 jts of 2" tubing to 1650'. Pumped 115 sks cement and 150# hulls down tubing to 1650'. Pulled tubing up to 815', pumped 100 sks cement w/100# hulls. Pulled up to 400' and circulated 75 sks cement to surface. Pulled tubing out of hole. Tied on to backside and pumped 60 sks cement. Shut in psi 100#. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 1529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: J. R. Oil Productions

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.


(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 9th day of May, 19 97

Irene Szersberg
Notary Public

My Commission Expires:



5-12-1997
RECEIVED
KANSAS COMPTROLLER
MAY 12 12 29 PM '97