

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barton County. Sec. 26 Twp. 20 Rge. 14W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE SE

Lease Owner Raymond Oil Company, Inc.

Lease Name WYLY Well No. 1

Office Address 410 Fourth National Bank Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed January 8, 19 63

Application for plugging filed January 8, (Verbal) 19 63

Application for plugging approved January 8, (Verbal) 19 63

Plugging commenced January 8, 19 63

Plugging completed January 8, 19 63

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Donald Truman, Russell, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3582 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	240'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug @245' 1/4 Sx. hulls and 25 Sx. cement.  
Plug @40' w/1/4 Sx. hulls and 15 Sx. cement.  
2 Sx. cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 18 1963

1-18-1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Raymond Oil Company, Inc.

Address 410 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Patrick R. Raymond (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Patrick R. Raymond

410 Fourth National Bank Building, Wichita 2, Ks.  
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of January, 19 63

Barbara A. Kennedy  
Notary Public.

My commission expires July 9, 1966

RAYMOND OIL COMPANY, INC.  
 No. 1 WYLY  
 NE-NE SE 26-20S-14W  
 Barton County, Kansas

ELEVATION: 1902 KB  
 1899 DF  
 1897 GL

Contractor: Raymond Oil Company, Inc. - Rig #7  
 Commenced: December 31, 1962  
 Completed: January 8, 1963


Casing Record:  
 8-5/8" @240' w/250 Sx.

Figures Indicate Bottom of Formation


<u>Formation</u>	<u>Depth</u>
Sand	165
Redbed and Shale	242
Redbed	810
Anhydrite	845
Redbed and Shale	1615
Lime and Shale	1995
Lime	2094
Lime and Shale	2885
Lime	3005
Lime and Shale	3109
Lime	3256
Shale and Lime	3268
Lime	3582 TD
 <u>TOPS</u>	
Anhydrite	804
Topeka	2817
Heebner	3160
Toronto	3182
Douglas	3200
Brown Lime	3278
Lansing Kansas City	3287
Base Kansas City	3500
Conglomerate	3520
Arbuckle	3568
Rotary Total Depth	3582

STATE OF KANSAS )  
 ) SS.  
 COUNTY OF SEDGWICK )

I hereby certify the above to be true and correct to the best of my knowledge.

  
 Patrick R. Raymond, Exec. Vice President

Subscribed and sworn to before me this 17th day of January, 1963.

  
 Notary Public

My commission expires:  
 July 9, 1966