

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.009.07167.0000

API NUMBER Drilled 11-19-44

LEASE NAME Taylor

WELL NUMBER #2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 26 TWP. 20 RGE. 14W (E) or (W)

COUNTY Barton

Date Well Completed

Plugging Commenced 8-2-93

Plugging Completed 8-4-93

TYPE OR PRINT
NOTICE: Fill out completoly
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rama Operating Company, Inc.

ADDRESS P.O. Box 159, Stafford, KS 67578

PHONE# (316) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Hubert Deines (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3600'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8"	889'	none
				5"	3600'	1675'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand & 5 sks cement at 3475'. Shot at 1675' & pulled to 1500'.

Pumped 30 sks w/150# hulls @ 1500'. Pulled rest of pipe. Welded 5 1/2" collar on 8 5/8".

Pumped 220 sks cement w/700# hulls. Plugging complete. 60/40 pos 10% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rama operating Company, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 12th day of August, 19 93

Irene Herzberg
Notary Public

My Commission Expires:



Form CP-4
Revised 05-88