


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 26 Twp. 20S Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines C NE NE NE
Lease Owner Clinton Oil Company
Lease Name Price Bondurant Well No. 2-D
Office Address 217 N. Water, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 2 19 69
Application for plugging filed Verbal Approval 19
Application for plugging approved Verbal Approval 19
Plugging commenced September 2 19 69
Plugging completed September 2 19 69
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	809'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,564 feet (rotary total depth) to 350 feet. Set plug at 350 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented to cellar with 10 sacks cement, 2 sacks cement in rathold.

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1969
CONSERVATION DIVISION
Wichita, Kansas
9-9-1969

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, INC.
Address 200 N. Main, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of September, 19 69

My commission expires April 21, 1971
Martha Hartpence Notary Public.

15.009.20403.0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Clinton Oil Company**


SEC. 26 T. 20S R. 14W
 LOC. C NE NE NE

FARM **Price Bondurant NO. 2-D**

COUNTY **Bafton**

TOTAL DEPTH **3,564'**
 COMM. **August 21, 1969**
 SHOT OR TREATED
 CONTRACTOR **H-30, INC.**
 ISSUED

COMP. **September 2, 1969**



CASING

20	10		
15	5/8"	809' cemented w/475 sx cement	ELEVATION 1899 KB
12	6		
13	5		

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	180
Shale & Red Bed	798
Anhydrite	827
Red Bed & Shale	1400
Salt	1600
Shale & Shells	1775
Shale & Lime	1935
Lime & Shale	2610
Lime	2653
Lime & Shale	3034
Lime	3130
Lime & Shale	3265
Lime	3338
Lime & Shale	3382
Lime	3425
Lime & Shale	3445
Lime	3510
Lime & Shale	3540
Lime	3564
Rotary Total Depth	3564

ELECTRIC LOG TOPS:

Anhydrite	797	+1102
Anhydrite Base	827	+1072
Topeka	2809	- 910
Toronto	3166	-1267
Heebner	3171	-1272
Douglas	3190	-1291
Brown Lime	3263	-1364
Lansing	3273	-1374
Base K.C.	3494	-1595
Conglomerate	3510	-1611
Arbuckle	3543	-1644
Log T.D.	3564	-1665
Rotary T.D.	3564	-1665

RECEIVED
 STATE CORPORATION COMMISSION
SEP 9 1969
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

Arlo B. Romer

 Arlo B. Romer

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 8th day of September, 1969.

Martha Hartpence

 Martha Hartpence-Notary Public

My Commission Expires:
 April 21, 1971