


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County. Sec. 26 Twp. 20 Rge. 14 E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines _____

NW NW NW
Lease Owner Brougher Oil Co.
Lease Name Janne #1 Well No. _____
Office Address Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2/8/77 _____ 19____
Plugging completed 2/11/77 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3557
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	258	none
				4 1/2"	3552	3001

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3525', mixed and ran 4 sacks cement. Installed stripper head, shot pipe at 2990', pulled 92 joints. Squeezed well with 2 sacks hulls, 20 sacks gel, released plug and ran 2 sacks hulls and 100 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

FEB 22 1977
2-22-1977

(If additional description is necessary, use BACK of COVER SHEET)
Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of Feb., 19 77

NOTARY PUBLIC
MARGARET MELCHER
Rice County, Ks.
My Comm. Exp. Feb. 15, 1979

Margaret Melcher
Notary Public.

My commission expires _____

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

15.009.20978.0000

1008 UNION NATIONAL BUILDING
WICHITA, KANSAS 67202

December 23, 1975

Company;	Brougher Oil, Inc.
Farm;	#1 Janne
Location;	NW NW NW
Section;	26-20-14W
County;	Barton County, Kansas
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	December 13, 1975
Compl;	December 22, 1975
Total Depth;	3557
Casing;	8 5/8" @ 258.10' w/225 sx. 4 1/2" @ 3552 w/100 sx

Figures Indicate Bottom Of Formations:

170	Sand
190	Shale
260	Shale & Sand Streak
405	Shale
785	Red Bed & Shale
818	Red Bed
844	Anhy
1505	Shale & Shells
1765	Shale & Lime
2275	Lime
2835	Lime & Shale
3155	Lime
3195	Lime
3340	Lime & Shale
3395	Lime
3495	Lime
3557	Lime

RECEIVED
STATE CORPORATION COMMISSION

OCT 27 1976

CONSERVATION DIVISION
Wichita, Kansas

I certify the above to be a true and correct copy of the driller's log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

K. T. Woodman
K. T. Woodman