


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Banking Building  
Wichita, Kansas

Barton County, Sec. 26 Twp. 20 Rge. (E) 14(W)  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SW NW SE  
Lease Owner Hinkle Oil Company  
Lease Name Wyly Well No. 2  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 7-8-52 19  
Application for plugging filed 7-14-52 19  
Application for plugging approved 7-14-52 19  
Plugging commenced 7-14-52 19  
Plugging completed 7-19-52 19  
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Rives  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5-1/2"	3665	3241'
				8 5/8	450	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole from 3570' to 3550' and ran 5 sacks of cement. Cleared hole. Had Halliburton pump in 20 sacks of mud and 225 sacks of cement into 8" pipe to seal off water. Plugging completed.

RECEIVED 8-7-1952  
STATE CORPORATION COMMISSION

CONSENT TO RECORD  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Maxwell Sheeks Hinkle Oil Company  
Address Gladwin, Kansas 914 Union National Bldg., Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
J. M. Hinkle (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Hinkle Oil Company By J. M. Hinkle  
914 Union National Bank Bldg.,  
(Address) Wichita, Kansas.

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 52

My commission expires Jan. 17, 1954.

Murmel A. Lupton  
Notary Public.

PLUGGING  
WELL SEC 26 TWP 20 RGE 14  
BOOK PAGE 31 LINE 22

WYLY NO. 2

SW/4 NW/4 SE/4 SECTION 26-20S-14W Barton County, Kansas

Rigging up Rotary Tools 6/26/52  
 Tearing down Rotary Tools 7/ 8/52

Ran 14 Jts. 8-5/8" 8 round thread,  
 24 lb. surface pipe. Set at 445'  
 and cemented with 350 sacks.  
 Ran 117 Jts. 5-1/2" 8 round thread,  
 14 lb. casing. Set at 3,629.50 and  
 cemented with 50 sacks.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand	0	41
Sand and Pea Gravel	41	205
Sand and Shale	205	305
Dakota Sand	305	385
Redbed	385	445
Redbed and Shale	445	700
Anhydrite	700	760
Shale and Sand Streaks	760	952
Shale and Sand	952	1332
Shale and Lime Streaks	1332	1695
Lime and Shale	1695	1830
Lime	1830	1935
Lime and Sandy Shale	1935	2034
Lime and shale	2034	2305
Shaled Lime	2305	2482
Shale and Lime Streaks	2482	2622
Shale and Lime	2622	3117
Sand	3117	3128
Lime	3128	3153
Sandy Lime	3153	3178
Lime	3178	3210
Shale and Sand and Lime	3210	3275
Lime and Shale	3275	3295
Lime	3295	3325
Lime and Shale	3325	3395
Lime	3395	3484
Shale and Lime	3484	3533
Lime	3533	3630
		TOTAL DEPTH

I, Don S. Packer, hereby certify that the above log is true and correct to the best of my knowledge and belief.

*Don S. Packer*

Subscribed and sworn to before me this 9th day of July, 1952.

*Wasson H. P. [Signature]*  
 Notary Public

My Commission Expires: September 24, 1955

RECEIVED  
 STATE CORPORATION COMMISSION

AUG - 7 1952

CONSERVATION DIVISION  
 Wichita, Kansas

PLUGGING  
 UNIT SEC 26 T 20 S 14 W  
 PAGE 31 LINE 20