

VP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply Co ~~15-145-01182-000~~
Complete Address: Box 562 Great Bend, Kansas **15-145-10084-0000 djk 8/31/18**
Lease Name Showalter Well No. 2
Location E $\frac{1}{2}$ E $\frac{1}{2}$ SE Sec. 6 Twp. 23 Rge. (E) (W) 17
County Pawnee Total Depth 4290
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Ace Pipe Pulling Co
Address: Great Bend, Kans License No. 2
Operation Completed: Hour 5PM Day 9 Month 7 Year 64

The Above well was plugged as follows:

8 5/8" 216' circulated with cement - 5 1/2" 4289' with 100 sax cement - Perforated 4228'.

Filled with sand to 4210', set 4 sax cement with dump bailer - pulled 2300' 5 1/2" - pumped hole full heavy mud (40 sax Gel), pumped wiper plug followed by 100 sax cement 2% chloride - cement to bottom cellar.

Mudding and cementing by Ace Company Pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edson Perry*
Well Plugging Supervisor

DATE 7/16/64
INV. NO. 9489-W