

KANSAS

FORM CP-3
Rev. 5-5-81STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT*R*API Number 15-159-21,212200 Colorado Derby Bldg.
Wichita, KS 67202Operator's Full Name Pioneer Operations Company, Inc.Complete Address Box 272, Russell, Kansas 67665Lease Name Hall Well No. 2Location C W/2 SW SE Sec. 31 Twp. 19 Rge. 9 (~~East~~) (West)County Rice Total Depth 3243'Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D & A ☒ X

Other well as hereafter indicated _____

Plugging Contractor Future Drilling, Inc. and Allied Cementing Co., Inc.Address Box 88, Russell, Kansas License No. _____Operation Completed: Hour: 4:45 AM Day: 16 Month: July Year: 19 81Plugging Operations attended by Agent? All ☐ Part ☐ None ☒ XThe above well was plugged as follows: 8-5/8"-217'-180 sacks

Hole circulated and filled with mud. 50 sacks 60-40 pozmix w/3% cal chl.
 pumped through drill pipe at 450'. 40 sacks 60-40 Poz. pumped through
 drill pipe at 240'. Hole filled with mud to 40'. Plug and $\frac{1}{2}$ sack hulls
 pushed to 40' and hole cemented to base of cellar with 10 sacks cement.
 Rathole cemented with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

6-17-81

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: James
Conservation Division AgentDATE 8-26-81INV. NO. 6296-W