

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 15 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name R. G. Smith

Complete Address 602 Rule Building, Wichita, Kansas 67202

Lease Name Schmit Well No. 1

Location SW NE SE Sec. 10 Twp. 19 Rge. 10 (E) (W) X

County Rice Total Depth 2950'

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co., Inc.

Address Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 5 PM Day 12 Month April Year 1968

The above well was plugged as follows:

Hole filled with sand to 2900' and cemented with 4 sacks. 5 sacks gel mud pumped through 4 1/2" casing at 600'. 25 sacks cement pumped through casing at 500'. 5 sacks gel mud pumped through casing at 300'. 25 sacks cement pumped through casing at 200'. Hole filled with mud to 40'. Rock bridge set from 40' to 30' and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 4/15/68  
INV. NO. 7584-4