

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Rice County. Sec. 15 Twp. 20 Rge. 10W(E) (W)

Location as "NE/CNW/SW" or footage from lines NW SW SE

Lease Owner J. L. Chew

Lease Name Linke Well No. 1

Office Address Lyons, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 23 1954

Application for plugging filed 19  

Application for plugging approved 19  


Plugging commenced March 11 1954

Plugging completed March 15 1954

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Ruell Durkee

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	158'	None
				5-1/2"	3234'	2611'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Ran 4 sacks of cement at 3205', filled hole with sand to 3135' and ran 4 sacks of cement. Mudded hole to 160', set a 10' rock bridge and ran 5 sacks of cement on top. Plugging completed.

RECEIVED  
STATE CORPORATION COMMISSION

APR 29 1954  
4-29-1954

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. L. Chew (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. L. Chew

By [Signature]  
Green Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of April, 1954

My commission expires Sept. 15, 1956 Shatter J. Volk Notary Public.

PLUGGING  
FILE 15 TWP 20 R10W  
BOOK PAGE 14 LINE 7

H. L. HERBEL

Well: Linke # 1

Commenced RD: 1-13-54  
Completed RD: 1-23-54

Total Depth 3425'

Casing: 158' 8 5/8" OD 24# 8 rnd thd  
3234' 5 1/2" ODNW SW SE  
Sec. 15-20-10  
Rice County

Elevation: 1843 RB

Contractor: Pam-Kar Drlg.  
Co.

STRATA	DEPTH		TOPS
Surface soil	5	Indian Cave	2380- 546
Sand & gravel	55	Emporia	2374--540
Sand & shale	97	Howard	2530- 696
Shale & shells	240	Severy Sand	2596- 762
Anhydrite	480	Heebner	2909-1075
Shale & shells	1480	Toronto	2926-1092
Shale & lime	1735	Oread	2940-1106
Broken Lime	1850	Brown Lime	3044-1210
Lime & shale	2084	Lansing	3067-1173
Shale & shells	2631	Simpson	3357-1523
Lime & shale	2788	Thin string of	
Lime, shale & chirt	2876	Arb. Dolomite	3403-1569
Shale & chirt	2918		
Shale & lime	3008		
Shale & lime	3084		
Shale, lime & chirt	3150		
Lime & shale	3253		
Shale & lime	3425		
Total Depth	3425		

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

**RECEIVED**  
STATE CORPORATION COMMISSION

APPROVED  
CONSERVATION DIVISION  
Wichita, Kansas

PAM-KAR DRILLING COMPANY, INC.  
BY

*Ralph B. McLaughlin*  
Ralph B. McLaughlin, Sec. Treas.

Signed and sworn to in my presence this 27th day of January, 1954, by Ralph B. McLaughlin, Sec-Treasurer of the Pam-Kar Drilling Company, Inc., a corporation in the State of Kansas.

*John C. Tully*  
Notary Public

My commission expires September 4, 1957.

PLUGGING  
FILE SEC 15 20 10a  
BOOK PAGE 14 LINE 7