

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rice County. Sec. 12 Twp. 21 Rge. 10 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW SW SW
Lease Owner Dozier Oil Company,
Lease Name Boy Well No. 1
Office Address Union National Bank Building, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-9-50 19
Application for plugging filed 12-9-50 19
Application for plugging approved 12-9-50 19
Plugging commenced 12-9-50 19
Plugging completed 12-9-50 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee, McPherson, Kansas.
Producing formation Depth to top 3447 Bottom 3447 Total Depth of Well 3447 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|-----|--------|--------|------------|
| | | 0 | 168 | 8-5/8" | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 160 feet to 20 feet for each plug set.

Used Halliburton plugs. Pushed plug to depth of 160' cemented 15-sacks cement through drill pipe, cemented one plug to 20' with 5-sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1950

12-13-1950

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Dozier Oil Company,
Address Union National Bank Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Rice, ss.
Stag Drilling Inc., (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *C. L. Dymall*
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of December, 1950
Orlando Miller
Notary Public.

My commission expires 3/1/51

22-1377-5 4-49-10M
PLUGGING
FILE SEC 16 T 21 R 10 W
BOOK PAGE 47 LINE 41

CONTRACTOR'S WELL LOG

Operator Dezier Oil Company Farm Name Boy #1
 Location SW NW NW Sec. 16-21-10, Rice County, Kansas.
 Pool Name _____ County Rice State Kansas.
 Commencement Date 11-29-50 Completion Date 12-9-50

Log of Well

| From | To | Formation | Deviation from Vertical | Remarks |
|------|------|-----------------------|-------------------------|---------|
| 0 | 140 | Surface Soil | | |
| 140 | 291 | Red Bed. | | |
| 291 | 401 | Anhydrite | | |
| 401 | 920 | Shale-Shells | 0° - 503' | |
| 920 | 1065 | Salt | 1/4° - 1000' | |
| 1065 | 1235 | Shale-Shells. | | |
| 1235 | 1475 | Lime-Shale | | |
| 1475 | 1640 | Broken Lime | 1/8° - 1500' | |
| 1640 | 1665 | Sand Lime | | |
| 1665 | 1705 | Lime-Shale. | | |
| 1705 | 1790 | Shale-Lime-Shells. | | |
| 1790 | 2270 | Shale-Shells | 0° - 2055' | |
| 2270 | 2548 | Lime-Shale. | | |
| 2548 | 2557 | Gas Sand. | | |
| 2557 | 2630 | Sand Lime. | | |
| 2630 | 2879 | Lime. | | |
| 2879 | 2884 | Heebner Shale. | | |
| 2884 | 2935 | Lime-Shale-Red Rock. | | |
| 2935 | 3017 | Shale-Lime. | | |
| 3017 | 3347 | Lime. | | |
| 3347 | 3377 | Congl. | | |
| 3377 | 3402 | Shandy Shale-Simpson. | | |
| 3402 | 3447 | Arb. | | |

Total Depth.

Set 168' (9)Jts). 8-5/8" surface pipe.

State of Kansas)
 County of Rice) SS

The undersigned certifies that to the best of his knowledge and belief the above facts are true and correct.

Stag Drilling Inc.,

by C. L. Dymall
 President.

Subscribed and sworn to before me this 12th day of December, 1950.

My Commission Expires.

3/1/51

PLUGGING
 FILE SEC-16-T-21R-182
 BOOK PAGE 47 LINE 4

Observed
 NOT RECORDED
 STATE CORPORATION FOR
 JAN X 8 1951
 COMMISSION FOR