

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD  
OR  
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission,  
800 Bitting Building,  
Wichita, Kansas

Rice County. Sec. 32 Twp. 19 S. Rge. 10 (E) 10 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines E/2, NE/4 - 660' from Skins 330' from Skins

Lease Owner Bradley Oil Co.

Lease Name S. Wendel Well No. 6

Office Address 402 Brown Bldg., Wichita, Kansas.

Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date, well completed May 9th 1936

Application for plugging filed May 8th 1936

Application for plugging approved May 8th 1936

Plugging Commenced May 8th 1936

Plugging Completed May 9th 1936

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 193

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - Morgan

Name of Conservation Agent who supervised plugging of this well Raymond Gear

Producing formation None Depth to top - Bottom ✓ Total Depth of Well 3378 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10"	180'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded from 3378 to approximate top and cement plug to surface.



(If additional description is necessary use BACK of this sheet)

Correspondence regarding this well should be addressed to Bradley Oil Co.

Address 402 Brown Bldg. Wichita Kansas

STATE OF Kansas, COUNTY OF Sedgewick, SS.

Claude Killon (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Claude Killon

402 Brown Bldg. Wichita Kan (Address)

SUBSCRIBED AND SWORN to before me this 9 day of May, 1936

My commission expires April 2, 1938

Robert Jones

Notary Public.

Wendel #6,

Bradley Oil Co.,

402 Brown Bldg.,

Wichita, Kansas.

E $\frac{1}{2}$  NB $\frac{1}{4}$  Sec. 32, 19S 10W,  
Rice County, Kansas.

Triangle Drilling Company, Contractor,

Rotary hole.

Commenced drilling 4-22-36.

Dry Hole.

0-50 surface sand and clay

50-180 sand, red rock and shale 10" surface casing set 180' cemented w/ 75 sax

180-240 red bed and shale

240-560 red bed, sand shale and shells

560-770 red bed, sand shale and shells

770-980 shale and shells

980-1275 salt shale and shells

1275-1605 shale and lime

1605-1625 shale and shells

1625-1650 sand

1650-1755 shale and shells

1755-1875 shale and lime

1875-1930 shells and shale

1930-2005 shale and lime

2005-2645 shale and lime

2645-2725 lime

2725-2785 lime and shale

2785-2905 lime

2905-3035 lime and shale

3035-3277 lime

3277-3289 lime and shale

3289-3300 lime and shale

3300-3378 lime

No shows

*Plugged and abandoned May 9, 1936*

PLUGGING	
FILE	SEC 32 T 19 R 10W
BOOK	PAGE 45 LINE 13