

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Pitting Building
Wichita, Kansas

RICE County. Sec. 17 Twp. 19 Rge. 10 (X) W (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner JAY BERGMAN OIL COMPANY

Lease Name BERGMAN FEE # Well No. 1

Office Address 425 Union Center Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed April 17 19 50

Application for plugging filed August 9, 19 56

Application for plugging approved August 14, 19 56

Plugging commenced September 25 19 56

Plugging completed September 31 19 56

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 3345 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	152'	
				5 1/2"	3345'	2617'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3273 to 3070 ft. Filled with mud
 3070 to 3040 ft. 6 sks. cement
 3040 to 235 ft. Mudded.
 235 to 225 ft. Rock bridge.
 225 to 165 ft. 25 sks. cement
 165 to 15 ft. Mud.
 15 ft. to cellar 5 sks. cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & S Pipe Pulling Co.
Address Box 192 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Harold Bergman (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Bergman
425 Union Center Bldg.
(Address)

SUBSCRIBED AND SWORN to before me this 14 day of September, 1956

My commission expires 12-1-56 Greta Brennan Notary Public.

REGISTERED
STATE CORPORATION COMMISSION
SEP 15 1956
CONSERVATION DIVISION
4-15-1956

PLUGGING
FILE SEC 17 T 19 R 10 W
BOOK PAGE 89 LINE 42


DRILLERS LOG

Company: Bergman Oil Co.
Farm: Bergman Fee No. 1
Sec: 17-19S-10W
Loc: SE SE SE
Rice County, Kansas
Contractor: Honaker Drilling Co.

Total Depth: 3348
Commenced: 4-3-50
Completed: 4-14-50

0	125	Sand	
125	155	Shells	8-5/8" casing cemented at 155
155	224	Shells & Shale	feet with 125 sacks cement and
224	459	Red Bed	1 sack calcium chloride.
459	517	Lime	
517	565	Red Bed & Shale	
565	890	Shale & Shells	
890	1100	Shale & Salt	
1100	1575	Lime & Shale	
1575	1670	Lime	
1670	1785	Lime & Shale	
1785	1955	Lime	
1955	2615	Lime & Shale	
2615	2715	Lime	
2715	2865	Lime & Shale	
2865	2890	Shale	
2890	2955	Sand & Shale	
2955	3150	Lime	5-1/2" casing cemented at 3348'
3150	3305	Lime & Shale	with 100 sacks cement.
3305	3348	Lime	
3348		TRD	

I hereby certify that this is a true and correct copy of the Drillers Log as taken from the original Daily Drilling Reports.


H. S. Forbes

Subscribed and sworn to before me this 25th day of September, 1956.

My Commission Expires: 6-25-59


Kenneth G. Fischer, Notary Public

PLUGGING
FILE SEC 17 T 19 R10W
BOOK PAGE 89 LINE 42

RECEIVED
COMMISSION
SEP 25 1956