

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Payment
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

Rice County. Sec. 12 Twp. 19 Rge. (E) 10 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW SE NE

Lease Owner G. W. Keyes Drilling Company, et al.

Lease Name Flora "A" Well No. 1

Office Address Ellinwood, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Small oil well-abandoned as

Date well completed July 26, 1947 dry

Application for plugging filed Oct. 27, 19

Application for plugging approved Oct. 27, 19

Plugging commenced Oct. 27, 19

Plugging completed Nov. 7, 19

Reason for abandonment of well or producing formation non-commercial well

If a producing well is abandoned, date of last production October 16, 1947

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Arbuckle Depth to top Bottom Total Depth of Well 3279 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface pipe		0	148	10 3/4	148	0
Oil String		0	3263	5 1/2	3263	2260

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled bottom of hole with crushed rock from 3279 to 3263 and cemented with 6 sacks at 3263', mudded to 200' and set rock bridge at 200', dumped 25 sacks cement at 200' mudded back to 15' set rock bridge and cemented with 5 sacks, cement returning to bottom of cellar.

11-21-1947

NOV 21 1947

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to G. W. Keyes Drilling Co.
Address Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

I, G. W. Keyes, Part Owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) G. W. Keyes

Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of November, 1947.

My commission expires February 10, 1951

George A. Meyer
Notary Public.



WELL LOG

Keyes Drilling Company et al, Owners - Flora A #1

NW SE NE Section 12, Township 19S, Range 10 West, Rice County, Kansas

Elevation 1721

Figures indicate bottom of formation

Pipe Record

10 3/4" set at 148'
5 1/2" set at 3263'

Tops corrected 3' to Derrick Floor

Topeka 2484
Heebner shale 2749
Base Oread 2781
Brown Lime 2874
Lansing 2899
Base K C Lime 3187
Chert Congl. 3243
Arbuckle Dol. 3257

0 to 109 clay & sand
193 shale
363 red bed
395 anhydrite
890 shale and shells
1055 salt and shale
1250 shale and broken lime
1500 lime and shale
1600 lime
1660 lime and shale
2235 shale and shells
2325 broken lime
2450 shale and lime shells
2488 shale
3178 lime
3240 shale and lime
3256 shale and congl.
3265 arbuckle lime
3265 total rotary depth REM

Rotary commenced 6-16-47
Rotary completed 6-27-47
Cable Tools Commenced 6-28-47
Cable Tools Completed 7-26-47

CABLE TOOL WORK

Moved in cable tools, drilled cement and cleaned out to total rotary depth. Drilled deeper.

3279 Lime
3279 Total Depth D & A

State of Kansas)
County of Barton) SS

I, G. W. Keyes, Part Owner of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well as filed and that the same are true and correct.

G. W. Keyes

Subscribed and Sworn to before me this 30th day of September, 1947.

George A. Meyer
Notary Public

My Commission expires February 10, 1951.

28 1947

PLUGGING
FILE SEC-12T-19-R10W
BOOK PAGE 142 LINE 45