


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Rice County. Sec. 7 Twp. 19 Rge. 10 (W)
Location as "NE/CNW/SW" or footage from lines N/2 SE NW
Lease Owner Icer Addis
Lease Name Karber "C" Well No. 2
Office Address Box 519 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed June 29 1961
Application for plugging filed July 3 1961
Application for plugging approved 19
Plugging commenced June 29 1961
Plugging completed " " 1961
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Jones at McPherson
Producing formation Depth to top Bottom Total Depth of Well 3371 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	250'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Bottom plug at 240' with 1/4 sack of hulls and 20 sacks of cement through drill pipe. Top plug at 35' with 1/2 sack of hulls and 10 sacks of cement. 2 sacks of cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION
JUL 10 1961 7-10-1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Triangle Drilling, Inc.
Address Box 519 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Donald D. Vaughan (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Donald D. Vaughan
Box 825 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd. day of July, 1961
Jessie Lee Dunn
Jessie Lee Dunn Notary Public.
My commission expires July 1, 1964



WELL LOG

COMPANY Icer Addis
 CONTRACTOR Triangle Drilling, Inc.
 FARM Karber "C" #2
 LOCATION N/2 SE NW of Section 7-19S-10W
 Rice County, Kansas
 SURFACE PIPE 8-5/8" cemented @ 250' with 175 sacks HA-5 cement
 PRODUCTION: D&A
 ELEVATION: 1775' K.B.
 COMMENCED: June 22, 1961
 COMPLETED: June 29, 1961

<u>FORMATION</u>	<u>DEPTH</u>
Surface clay	40
Sand and Shale	160
Shale	243
Redbed	535
Anhydrite	548
Shale & Shells	1300
Limestone & Shale	2631
Limestone	2926
Shale	3016
Limestone	3337
Conglomerate	3369
Arbuckle	3371

RECEIVED
 STATE CORPORATION COMMISSION

JUL 10 1961

CONSERVATION DIVISION
 Wichita, Kansas

FORMATION TOPS

Anhydrite	535 (+1240)	drillers
Topeka	2631 (- 856)	
Heebner	2894 (-1119)	
Toronto	2917 (-1142)	
Brown Lime	3016 (-1241)	
Lansing	3036 (-1261)	
Conglomerate	3337 (-1562)	
Arbuckle	3369 (-1594)	
Total Depth	3371 (-1596)	

A F F I D A V I T

STATE OF KANSAS, COUNTY OF BARTON, SS.

I, Donald D. Vaughan, Petroleum Geologist, being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.


 Donald D. Vaughan

Subscribed and sworn to before me this 6th day of July, 1961.


 Dorothy B. John, Notary Public

My commission expires: June 18, 1963